

## CITY of NOVI CITY COUNCIL

Agenda Item F August 28, 2017

**SUBJECT:** Approval to authorize D&D Water and Sewer Inc. to install a fire hydrant along the frontage of 43651 Nine Mile Road, in the amount of \$21,900.

**SUBMITTING DEPARTMENT**: Department of Public Services, Water and Sewer Division

CITY MANAGER APPROVAL:

EXPENDITURE REQUIRED	\$ 21,900
AMOUNT BUDGETED	\$ 21,900
LINE ITEM NUMBER	592-592.00-976.042

## **BACKGROUND INFORMATION:**

This work involves the installation of a fire hydrant on the south side of Nine Mile, across from Montebello Estates, to provide additional fire suppression coverage in this area. To maintain the integrity of the Nine Mile Pavement, the new 8-inch water main will be installed via directional drilling methods under the road.

It is anticipated that this project will be completed by fall 2017.

**RECOMMENDED ACTION:** Approval to authorize D&D Water and Sewer Inc. to install a fire hydrant along the frontage of 43651 Nine Mile Road, in the amount of \$21,900.









1 inch = 200 feet



City of Novi

Engineering Division

Department of Public Services
26300 Lee BeGole Drive
Novi, MI 48375
cityofnovi.org

# **Proposal**

# D & D Water & Sewer, Inc.

7371 Haverhill Lane Canton, MI 48187

Contact: Mark DiMichele, PE

Phone: 734-397-3386 Fax: 734-397-8486

Quote To: City of Novi Job Name: 9 Mile Rd Hydrant Extension

Scott Roselle

Date of Plans:
Revision Date:

Phone: Fax:

Cell 734-368-2375

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	AMOUNT
100	Install Fire Hydrant	1.00	EA	3,500.00	3,500
150	Install 8 in Water Main Dir Drill	120.00	LF	95.00	11,400
170	Connection to existing water main	1.00	EA	3,500.00	3,500
200	Traffic Control	1.00	LS	3,500.00	3,500

GRAND TOTAL \$21,900.00

### NOTES:

NOTES:

**EXCLUSIONS:** 

PERMITS, BONDS, INSPECTION FEES, CONSTRUCTION STAKING, DUST CONTROL, COMPACTION TESTING, UNDERCUTS OF UNSTABLE SOILS, TOPSOIL, LANDSCAPING RELATED WORK, DEWATERING, DEMOLITION, REMOVALS

HYDROSTATIC TESTING IS INCLUDED.

SILT FENCE AND SEDIMENTATION CONTROL IS NOT INCLUDED

Water Supply and/or Hydrant Meter for Drilling Fluid is not included.